

Environmental Health: Contaminated Land

Consultee response · dated 2026-06-20

1. The Phase 2 report identifies hydrocarbons (up to 3,400 mg/kg TPH) and elevated lead in made ground to 2.5m in the former fuel storage area. Remediation is required in the form of excavation and off-site disposal of approximately 1,900 cubic metres, and gas protection measures to Blocks B and C.
2. Indicative remediation cost in the applicant's report: £640,000 to £820,000. Conditions 9 to 12 secure remediation, verification and a discovery strategy.