

Structural Condition Survey: Summary

Survey / technical · dated 2026-04-30

1. Warehouses 1 and 3 are in fair condition. Warehouse 2 has localised decay to timber joists at the northern gable and significant deflection to the second floor. Estimated structural repair budget £410,000. Roof coverings require replacement (£290,000). Asbestos survey identified ACM in the boiler room and ceiling boards.
2. Cast iron columns show no evidence of cracking. Floor loading capacity is 5kN/sqm, suitable for residential.